

## PART 1 - GENERAL

### 1.1 SUMMARY

- A. This Section includes the following:
  - 1. Soil Preparation.
  - 2. Planting.
  - 3. Staking and Guying.
  - 4. Cleanup.

### 1.2 OBSERVATION SCHEDULE

- A. Design/Builder shall be responsible for notifying the University, in advance, for the following observations, according to the time indicated:
  - 1. Pre-construction conference – seven (7) days
  - 2. Tree tagging at nursery (trees 24" box size and larger) – 48 hours
  - 3. Final grade, soil preparation and planting area layout review - 72 hours
  - 4. Plant materials review - 48 hours
  - 5. Plant layout review - 48 hours
  - 6. Planting operations - 48 hours
  - 7. Completed planting (Pre-maintenance) walk through – seven (7) days

## PART 2 - PRODUCTS

### 2.1 WEED BARRIER FABRIC

- A. Spun or woven, non-degrading geotextile fabric that blocks 95% of weed growth and is permeable to air, water, gases and fertilizer.

### 2.2 ROOT BARRIER

- A. Manufacturers: Deep Root Corp. model UB 18-2, Century Products model CP, or equal.

### 2.3 TREE TRUNK PROTECTOR

- A. Manufacturers: Deep Root Corp model Arbor Guard, Century Products model Century Tree Guard, or equal.

## PART 3 - EXECUTION

### 3.1

- A. Landscape shall conform to University Landscape Standards.
- B. Landscape design and materials shall be reviewed and approved by the University Police for security purposes.

END OF SECTION